Hyper-K Liner and PMT Support

Hide-Kazu TANAKA (ICRR, University of Tokyo)

for the Cavity and Tank WG

HK 2nd Open Meeting, Jan. 14th, 2013


Monday, January 14, 13

Outline

- Introduction
- Updates from the last meeting
 - Water piping, cable layout of online system, calibration holes, manholes
- On-going work...
- Discussion
 - HK tank compartments / segmentation walls

Introduction

Schematic View of the Hyper-Kamiokande




Key parameters on the baseline design


- Depth of tank water: 48m
- Cavern size: $48m(W) \times 54m(H) \times 250m(L) \times 2$ caverns
- Optically separated compartments: 5x2 = 10
- Water Volume:
 - •Total: 0.496x2=0.992 Megaton
 - ID volume: 0.74 Mton
 - Fiducial Volume: $0.056 \times 10 = 0.56$ Mton (25 x Super-K)
- PMT
 - ID: 99,000 20" PMTs (20% photo-coverage)
 - OD: 25,000 8" PMTs (same coverage as SK)

Conditions for the PMT support design

	Parameters	Remark
PMT total weight	Inner (20''): 29.8kg Outer (8''): 3.7kg	Everything around PMT (PMT, housing, cable, mounting parts, etc.)
PMT cable	Inner: 10m long, 2kg Outer: 10m long, 2kg	Cable from hub to PMT
PMT housing	[Inner] Housing weight: 15kg, Mounting parts: 0.35 kg, Buoyancy: 2.5kg	
	[Outer] No housing	
	Inner: 10m long, 2kg Outer: 10m long, 2kg	Cable between hubs
Hub	Dimension: 500x500x150, Weight: 5kg Buoyancy: 37.5kg	

Drawing of the tank






Updates from last mtg

- Deck load capacity defined to be 100 kg/m² at safety-factor 2.0 (consistent with SK)
- Preliminary design
 - PMT layout (inner and outer detectors)
 - Online system layout (cable, electronics),
 - Water pipe layout,
 - Calibration holes,
 - Manholes


PMT layout


PMT layout

- Number of PMTs
 - ID: ~99,000 of 20" PMTs (20% photo-coverage)
 - OD: ~25,000 of 8" PMTs (same coverage as SK)



PMT layout





- Inner PMTs (20"): 990 mm apart
- Outer PMTs (8"): 1980 mm / 1485 mm apart

Online System

Cables routing for Online System


- —: Cable for inner PMT
- ----: Cable for outer PMT
 - —: Network/Power cable
 - : Hub / Front End Electronics
 -) : Inner PMT (20'')
 -) : Outer PMT (8'')

One hub can handle 24 PMTs. Hubs are daisy-chained by network/ power cables to reduce the number of cables come out of tank.

960mm

Electronics Hut

- Electronics huts are in "Observation Tunnels"
 - No electronics hut on the deck




Observation tunnels are connected to the deck. Each compartment has one Observation Tunnel where the electronics/computers are installed.

Water Pipe

Water Pipe Layout

- Water inlet on bottom and outlet on top
- Inlets/outlets on barrel give additional control of water flow
- Number of water pipes / compartment
 - Inner Detector
 - Top (outlet): 18, Bottom (inlet): 18, Barrel (inlet/outlet): 30 x 2
 - Outer Detector
 - Top (outlet): 4, Bottom (inlet): 4, Barrel: (inlet/outlet): 10 x 2



Barrel pipe layout






Figure shows 1/4 of a compartment

Inner: 8083.3 mm apart in z-dir Outer: 24250 mm apart in z-dir



Calibration Holes and Manholes

Calibration hole layout




•: Calibration hole


- blue: I ton load capacity (for main calib systems)
- red: 100 kg load capacity (for sub/movable calib systems)
- •Calibration holes aligned along with tank axis, each hole located 3m apart.
- •~50 calib holes in one compartment.
- •Calib nozzle extended into inner detector volume (4m long).
- •Hole diameter 22.2cm ϕ (identical to SK)₂₀

Manholes

- Aimed to use for access inside the tank for maintenance of detector, etc.
- Manholes located at bottom of the tank, and connected to "4th-stage approach tunnel".



Manhole dimensions



 Manhole diameter: ~Imφ (I.5m at maximum) and ~3.8m long

On-going work

On-going work

- "Wire option" for PMTs support (like LBNE)
 - will be available in a few months
- Tank water leak detection/draining system
 - Note: drain system for water from rock has already been designed.
- PMT housing design/prototype & implosion test
- Establish the details of construction procedure of the tank, and estimate the overall cost.
 - by end of January
- Technical document of the baseline design of tank.
 - Doc.vl (in Japanese) by end of January

Discussion

Segmentation walls?

- Removing/reducing the segmentation walls is an option to "optimize" the project cost.
- If we remove all segmentation walls, the total PMTs cost is reduced by ~23% (~6 billion yen).
- Also, lead reduction of other costs:
 - Reduce the costs of PMT support structure, PMT housing, readout electronics, cables, and shorten the tank construction schedule (final const estimation will be available in this month)
- -> Large impact to the tank construction cost.
- Would start discussion with Physics WGs on whether this can be an option in physics point of view.

Summary

- Details of tank design have been made for:
 - PMT layout, online system cable/electronics layout, water system piping, calibration holes, manholes
- Removing/reducing the number of segmentation walls will make a large impact to the cost of tank construction.
 - \rightarrow Would consider this option seriously.
 - → Need physics sensitivity studies.