# SUBARUPRIMEFOCUSSPECTROGRAPH

#### Updates of the next-generation Subaru facility instrument under commissioning









#### Naoyuki Tamura [Kavli IPMU by 3/31 → Subaru, NAOJ from 4/1] On behalf of PFS collaboration



Mar 8 2023 JST @Kavli IPMU 学術変革領域 FY2022 シンポジウム Prime Focus Spectrograph





# **PFS** subsystems distribution



#### PFS commissioning has been underway.



# **Engineering First Light in Sep 2022**

Successfully observed many stars simultaneously by intentionally positioning the fibers on the targets.

Wavelength (630-970nm

60

300s exposure of stars in an NGC 1980 field w/ SM1 red camera

# Now two fiber cables & two spectrograph modules in place

Cable B1 & B2

on the telescope spider

Successful installation of 2<sup>nd</sup> Fiber Cable (Cable B2) in April 2022.



- Completed installing SM3 in early Nov 2022.
- Started its operation right away according to the good results of post-installation tests.

# The observation in Nov 2022 with doubled multiplicity: $\sim 600 \rightarrow \sim 1200$

Two more modules to come for the full multiplicity of ~2400

300s exposure of stars in an NGC 1980 field w/ SM1 & SM3 blue cameras



#### 8mm between adjacent Cobras

#### Fiber positioning accuracy

- Accurately predict (x,y) from  $(\alpha, \delta)$ .
- Accurately move the fiber to requested (x.y). 2.



x (mm)

#### Raster scan

To generate a 2D map of flux coming into the instrument around each fiber.

40cm

# a offect of flux poak from the middle is a



# The fiber diameter is equivalent to 100um

- 1".13@Field center
- 1".03@Field edge

Residual [um]

#### Fiber positioning accuracy

7.5

7.0

5.0

- 4.5



#### Systematic errors are dominant.

- Translational/rotational offset
   Some issues in the field acquisition and/or guiding?
- Scale error
  - ← Inaccurately modeled?

After numerically subtracting these offsets and scale error.

- Furthermore, averaging the errors
- from 10 sets of raster scan data.

#### Takeaways:

- The error seems dominated by the large-scale & small-scale systematics. Minimizing these is the priority.
- The contribution from the positioner's stochasticity seems very little.

## The fiber diameter is equivalent to 100um

- 1".13@Field center
- 1".03@Field edge

#### Fiber positioning accuracy

7.5

6.0

- <u>- -</u> - magnitude" |

5.0

4.5

4.0



#### Systematic errors are dominant.

- Translational/rotational offset ← Some issues in the field acquisition and/or guiding?
- Scale error
  - Inaccurately modeled?
- After numerically subtracting these  $-6.5 \frac{15}{9}$  offsets and scale error.
  - Furthermore, averaging the errors from 10 sets of raster scan data.

#### Takeaways:

- The error seems dominated by the large-scale & small-scale systematics.
  - Minimizing these is the priority.
- The contribution from the positioner's stochasticity seems very little.

#### The fiber diameter is equivalent to 100um

- 1".13@Field center
- 1".03@Field edge

#### Fiber positioning accuracy



#### Fiber positioning sequence



1. Accurately predict (x,y) from  $(\alpha, \delta)$ .

- 2. Accurately move the fiber to requested (x.y).
  - Iterative process between PFI and MCS: Measure the current positions, calculate deltas, and move the fibers.
  - 12 iterations are applied but improvement seems little after ~7<sup>th</sup> iteration.
    - >95% success rate is now stably achieved with 4.8s MCS exposure.
    - The processing time of each iteration is one vital engineering item:
      - ~400s/~270s by 12/7 iterations, respectively.
      - Detailed profiling & optimization
         are needed, while MCS data I/O
         seems major contribution





#### Data processing



Updates are applied to the pipelines continuously.

→ <u>Weekly</u> integration test: 2D (Princeton), 1D (LAM) & <u>End-to-end (IPMU)</u>



#### <u>Current status:</u>

- The pipeline (Lupton, Price+) is getting to be able to process data from engineering observations all the way down to flux calibration that is being developed at NAOJ (Yamashita, Mineo+).
- 2D PSF modeling as a key to very good sky subtraction still needs substantial development, while the spectrograph part seems quite well modeled already (Caplar, Hayashi, Yabe, 'PFI/DCB (fiber 255, angle=26.1')
- Useful QA plots are be those for accuracies of<sup>1</sup> calibration and sky sub appropriate tools neec (Hamano, Tanaka, Yabe,<sup>0</sup> Siddiqu<sup>200</sup> Price+)<sup>400</sup>



















# Updated timeline from now onward



#### Successful Cable B3 installation on Feb 7-8



One more cable is remaining. It will be a big job again but should now be a low-risk process:

- The cable is already at the Subaru summit.
- The earlier 3 cables were successfully installed.
- Most of the Daycrews and PFS members are familiar with the installation process.



# NIR Cameras #2,#3, #4 (N2-4) at JHU

#### • N2:

- All tests were done well, except for a sanity check of image quality after focus offset correction work.
- Documentation for the preship review on 3/13.
- N3:
  - All tests were done well, except for the focus offset correction work and subsequent sanity check of image quality.
  - Hope it will be "ready" soon.
- N4:
  - The cryostat assembly is done. Next is baking, with pumping and then cooling for tests.
  - The detector characterization is ongoing in the test dewar.
- Near-term goal is to deliver N2 to Subaru in March (and let N3 follow that soon).





# Spectrograph System (SpS) at LAM

- Tests of the 1<sup>st</sup> NIR camera (N1) as part of Spectrograph Module #2 (SM2) are ongoing.
  - N1 itself was fully assembled and tested at JHU, passed the preship review and was shipped to LAM.
  - The image quality at LAM looks as good as at JHU even with the system at 5°C in the chamber to simulate the operating condition at Subaru.
  - There were issues on the ion pumps ... but the pumps were replaced and the operation has been recovered.
- The assembly & test of the remaining visible cameras are also ongoing.
- Aiming at the delivery to Subaru of SM2 (BRN) & SM4 (BR) by mid July (although getting tight)

Visible camera under metrology







# Updated timeline from now onward

**EDR: Engineering Data Release** 



#### Science with PFS in the dark sector of the universe

Comprehensive challenges to the major questions of modern astronomy & cosmology by three pillar survey components:

- PFS large-sky survey in the framework of Subaru Strategic Program (SSP).
  - ~360 nights for ~5 years
  - Three pillars
    - Cosmology
    - Galaxy & AGN evolution
    - Galactic Archaeology

#### <u>Timeline:</u>

- System integration & survey planning are ongoing.
- On-sky commissioning from late 2021 to 2023 end.
- Science operation from 2024.
- \$100M project, \$1M shortage



Testing ACDM	Assembly history of galaxies	Importance of IGM
<ul> <li>Nature &amp; role of neutrinos</li> <li>Expansion rate via BAO up to z=2.4</li> <li>PFS+HSC tests of GR</li> </ul>	<ul> <li>PFS+HSC galaxy association</li> <li>Absorption probes with PFS QSOs and HSC host galaxies</li> </ul>	<ul> <li>Search for emission from stacked spectra</li> <li>dSph as relic probe of reionization</li> </ul>
<ul> <li>Curvature of space: Ω<sub>K</sub></li> <li>Primordial power spectrum</li> <li>Nature of DM (dSphs)</li> </ul>	• Stellar kinematics and chemical abundances – MW & M31 assembly history	feedback • Past massive star IMF from element abundances
<ul><li>Search of MW dark halo</li><li>Small-scale tests of structure growth</li></ul>	<ul> <li>Halo-galaxy connection: M<sub>*</sub>/M<sub>halo</sub></li> <li>Outflows &amp; inflows of gas</li> <li>Environment-dependent evolution</li> </ul>	<ul> <li>Physics of cosmic reionization via LAEs &amp; 21cm studies</li> <li>Tomography of gas &amp; DM</li> </ul>

# PFS science meeting @Kashiwa campus, Mar 2-3

Active & productive in-person+Zoom discussions to brush up the survey plan and proposal of PFS SSP.



PFS will be a very powerful tool to find crucial evidence for the dark matter profile around dwarf galaxies (see e.g. Hayashi's talk).



# PFS instrumentation is now back on the home stretch.

- Engineering observations
  - Engineering First Light in Sep 2022
  - Fiber positioning accuracy is getting better. Minimizing the systematic errors that
    - dominate the accuracy is next priority.

#### Ongoing hardware development

SM2 is being tested at LAM with the NIR camera. 3 other NIR cameras are being tested at JHU,

#### Timeline

- Install Cable B4 on the telescope in May. Install 1 NIR cameras by mid April, and the rest of SpS in June-July.
  - NIR first light in the April run.
  - 1<sup>st</sup> run with the full hardware in July.
- Open-use readiness review in Jan 2024 for science operation from S24B.











- ✓ Official web site <u>https://pfs.ipmu.jp/</u>
- Membership registration <u>https://pfs.ipmu.jp/research/regist\_collab.html</u>
- ✓ Blog <u>https://pfs.ipmu.jp/blog/</u>
- ✓ Instagram <u>https://www.instagram.com/pfs\_collaboration/</u>